ZHONGHUA SECONDARY SCHOOL
PRELIMINARY EXAMINATION 2021
SECONDARY 4 EXPRESS

Candidate's Name	Class	Register Number

ADDITIONAL MATHEMATICS 4049/01

PAPER 1

13 Sep 2021
2 hours and 15 minutes

Candidates answer on the Question Paper.

READ THESE INSTRUCTIONS FIRST

Write your name, class and register number on all the work you hand in.
Write in dark blue or black pen on both sides of the paper.
You may use an HB pencil for any diagrams or graphs.
Do not use paper clips, glue or correction fluid.

Answer **all** questions.

If working is needed for any question, it must be shown with the answer.
Omission of essential working will result in loss of marks.
The use of an approved scientific calculator is expected, where appropriate.
If the degree of accuracy is not specified in the question, and if the answer is not exact, give the answer to three significant figures. Give answers in degrees to one decimal place.
For π, use either your calculator value or 3.142, unless the question requires the answer in terms of π.

The number of marks is given in brackets [ ] at the end of each question or part question.
The total of the marks for this paper is **90**.

Setter: Mr Ardy Taniwan
Vetted by: Mr Poh Wei Beng

For Examiner's Use
90

This question paper consists of **18** printed pages (including this cover page)

PartnerInlearning
354
www.testpapersfree.com

Downloaded from SingaKids.com

$10e^{-2t} - 3 > -3$

Hence $v > -3$

PartnerInlearning
353
www.testpapersfree.com

Downloaded from SingaKids.com

1. ALGEBRA

Quadratic Equation

For the equation $ax^2 + bx + c = 0$

$$x = \frac{-b \pm \sqrt{b^2 - 4ac}}{2a}$$

Binomial expansion

$$(a+b)^n = a^n + \binom{n}{1}a^{n-1}b + \binom{n}{2}a^{n-2}b^2 + \cdots + \binom{n}{r}a^{n-r}b^r + \cdots + b^n,$$

where n is a positive integer and $\binom{n}{r} = \frac{n!}{r!(n-r)!} = \frac{n(n-1)\ldots(n-r+1)}{r!}$

2. TRIGONOMETRY

Identities

$$\sin^2 A + \cos^2 A = 1$$
$$\sec^2 A = 1 + \tan^2 A$$
$$\operatorname{cosec}^2 A = 1 + \cot^2 A$$
$$\sin(A \pm B) = \sin A \cos B \pm \cos A \sin B$$
$$\cos(A \pm B) = \cos A \cos B \mp \sin A \sin B$$
$$\tan(A \pm B) = \frac{\tan A \pm \tan B}{1 \mp \tan A \tan B}$$
$$\sin 2A = 2\sin A \cos A$$
$$\cos 2A = \cos^2 A - \sin^2 A = 2\cos^2 A - 1 = 1 - 2\sin^2 A$$
$$\tan 2A = \frac{2\tan A}{1 - \tan^2 A}$$

Formulae for ΔABC

$$\frac{a}{\sin A} = \frac{b}{\sin B} = \frac{c}{\sin C}$$
$$a^2 = b^2 + c^2 - 2bc\cos A$$
$$\Delta = \frac{1}{2}bc\sin A$$

PartnerInlearning
355
www.testpapersfree.com

Downloaded from SingaKids.com

1 **Do not use a calculator in this question.**

(a) Given that A and B are acute angles such that $\sin(A-B)=\frac{3}{8}$ and $\sin A\cos B=\frac{5}{8}$, find the value of

(i) $\cos A\sin B$, [2]

(ii) $\cot A\tan B$. [2]

PartnerInlearning
356
www.testpapersfree.com

Downloaded from SingaKids.com

1 **(b)** Given that $\tan A = -\frac{3}{4}$ and $\cos B = \frac{5}{13}$, where A is an obtuse angle and B is a reflex angle, find

(i) $\cos 2A$, [2]

(ii) $\tan(A-B)$. [2]

PartnerInlearning
357
www.testpapersfree.com

Downloaded from SingaKids.com

2 Given that $\sqrt{p+q\sqrt{8}} = \dfrac{9}{4-\sqrt{8}}$, where p and q are rational numbers, find the values of p and q. [4]

PartnerInlearning
358
www.testpapersfree.com

Downloaded from SingaKids.com

3 Baking powder is poured onto a flat surface at a constant rate of 2π cm^3s^{-1} and formed a right circular cone. The radius of the cone is always $\frac{1}{18}$ of its height. Find the rate of change of the radius of the cone after 3 seconds of pouring. [5]

PartnerInlearning
359
www.testpapersfree.com

Downloaded from SingaKids.com

4 **(a)** The quantity, N, of a micro-organism multiply themselves under ideal conditions based on the formula $N = N_0 e^{\frac{t}{7}}$ where N_0 is a constant and t is the time interval in minutes.

Find the time taken for the quantity of the micro-organism to be twice of the initial quantity. [3]

(b) In order to obtain a graphical solution for the equation $x = -2\log_9(3-x)$, a straight line graph has to be drawn on the graph of $y = 3^{-x}$.

Find the equation of the straight line that need to be drawn. [3]

PartnerInlearning
360
www.testpapersfree.com

Downloaded from SingaKids.com

5 The roots of a cubic equation $F(x)=0$ are -1, 2 and 5. When $F(x)$ is divided by $x-3$, the remainder is 30.


(i) Find the remainder when $F(x)$ is divided by $x+3$. [4]

(ii) Solve the equation $F\left(\sqrt{m}\right)=0$. [2]

PartnerInlearning
361
www.testpapersfree.com

Downloaded from SingaKids.com

6 **(a)** The graph below shows part of a trigonometric function.



(i) State the amplitude and period of the function. [2]

(ii) Explain why the graph cannot represent the tangent function. [1]

PartnerInlearning
362
www.testpapersfree.com

Downloaded from SingaKids.com

6 **(b) (i)** Sketch the graph of $y = -4\sin 3x + 2$ for $0° \le x \le 360°$. [3]

(ii) State the number of solutions for the equation $5 = -4\sin 6x + 2$ for $0° \le x \le 360°$.

[1]

PartnerInlearning
363
www.testpapersfree.com

Downloaded from SingaKids.com

7 A curve has the equation $y = f(x)$, where $f(x) = \dfrac{5x+11}{x^2+3}$.

(i) Find the equation of normal to the curve at the point where the curve passes through the y-axis. [6]

(ii) Determine the range of values of x for which $f(x)$ is a decreasing function. [3]

PartnerInlearning
364
www.testpapersfree.com

Downloaded from SingaKids.com

8 **(i)** Prove the identity $\frac{\sin 2x}{\sin x} - \frac{\cos 2x}{\cos x} = \sec x$. [3]

(ii) Solve the equation $\frac{2\sin 2x}{\sin x} - \frac{2\cos 2x}{\cos x} = 3\cos x + 1$ for $0° < x < 360°$. [4]

PartnerInlearning
365
www.testpapersfree.com

Downloaded from SingaKids.com

9 A particle travels in a straight line so that t seconds after passing a fixed point O with a velocity of 15 cms^{-1}, its acceleration a cms^{-2} is given by $a = k - 2t$ where k is a constant. The particle reaches maximum velocity in 1 second.

Find

(i) the value of k, [1]

(ii) an expression for the velocity, v, in terms of t, [3]

(iii) the distance travelled in the first 10 seconds. [4]

PartnerInlearning
366
www.testpapersfree.com

Downloaded from SingaKids.com


10 $f(x)$ is such that $f'(x) = -2\sin 4x + \cos 3x$.

Given that $f(0) = 0$, find the exact value of $f\left(\frac{\pi}{4}\right)$. [6]

PartnerInlearning
367
www.testpapersfree.com

Downloaded from SingaKids.com

11 The diagram shows a triangle PQR circumscribed in a circle.
$PQ = 10$ cm , $QR = x$ cm and PR is the diameter of the circle.



(i) Explain why the area of shaded regions, A cm^2, is $25\pi + \frac{\pi}{4}x^2 - 5x$. [4]

(ii) Given that x can vary, find the minimum area of the shaded region. [3]


PartnerInlearning
368
www.testpapersfree.com

Downloaded from SingaKids.com

12 Given that the expansion of $\left(1+\frac{x}{2}\right)^n(3-2x)$ up to the first three terms, in ascending powers of x, is $h+10x+kx^2$, find the values of h, k and n. [7]

PartnerInlearning
369
www.testpapersfree.com
Downloaded from SingaKids.com

13 The diagram below shows a trapezium $OABC$, where O is the origin.



The equation of AO is $y = 4x$ and the equation of OC is $y + 3x = 0$.
The line through A perpendicular to OA meets y-axis at B and BC is parallel to AO.

Given that the length of OA is $\sqrt{1700}$ units, find the coordinates of A, of B and of C. [10]

PartnerInlearning
370
www.testpapersfree.com
Downloaded from SingaKids.com

Continuation of working space for Question 13.

~~~ *End of Paper* ~~~

PartnerInlearning
371
www.testpapersfree.com

Downloaded from SingaKids.com
~~~

Answers:

1ai. $\frac{1}{4}$

1aii. $\frac{2}{5}$

1bi. $\frac{7}{25}$

1bii. $\frac{33}{56}$

2. $p=\frac{243}{8}$ $q=\frac{81}{8}$

3. $\frac{1}{9}$ cm/s

4a. 4.85 minutes

4b. $y=3-x$


5i. 300

5ii. $m=4$ $m=25$

6ai. amplitude = 4.5 period = $\frac{2}{3}\pi$

6aii. Because the graph is continuous
Because the graph has maximum and minimum
Because the graph does not have asymptote lines

6bi.



6bii. 12 solutions

7i. $y=-\frac{3}{5}x+\frac{11}{3}$

7ii. $x<-5$ or $x>\frac{3}{5}$

8ii. 48.2°, 180°, 311.8°

9i. $k=2$

9ii. $v=-t^2+2t+15$

9iii. 200 m

10. $\frac{1}{6}\sqrt{2}-1$

11ii. 70.6 cm^2

12. $h=3$ $n=8$ $k=13$

13. $A(10, 40)$
$B(0, 42.5)$
$C\left(-\frac{85}{14}, \frac{255}{14}\right)$

PartnerInlearning
372
www.testpapersfree.com
Downloaded from SingaKids.com

ZHONGHUA SECONDARY SCHOOL
PRELIMINARY EXAMINATION 2021
SECONDARY 4 EXPRESS

Candidate's Name	Class	Register Number

ADDITIONAL MATHEMATICS 4049/02

PAPER 2

14 September 2021
2 hours 15 minutes

Candidates answer on the Question Paper

READ THESE INSTRUCTIONS FIRST

Write your name, class and register number on all the work you hand in.
Write in dark blue or black pen on both sides of the paper.
You may use an HB pencil for any diagrams or graphs.
Do not use staples, paper clips, glue or correction fluid.

Answer **all** the questions.
Give non-exact numerical answers correct to 3 significant figures, or 1 decimal place in the case of angles in degrees, unless a different level of accuracy is specified in the question.
The use of a scientific calculator is expected, where appropriate.
You are reminded of the need for clear presentation in your answers.

The number of marks is given in brackets [ ] at the end of each question or part question.
The total number of marks for this paper is **90**.

For Examiner's Use
90

Setter: Ms Lee SK
Vetted by: Mr Poh WB

This question paper consists of **20** printed pages (including this cover page)

PartnerInlearning
373
www.testpapersfree.com

Downloaded from SingaKids.com

1. ALGEBRA

Quadratic Equation

For the equation $ax^2 + bx + c = 0$,

$$x = \frac{-b \pm \sqrt{b^2 - 4ac}}{2a}$$

Binomial Theorem

$$(a+b)^n = a^n + \binom{n}{1}a^{n-1}b + \binom{n}{2}a^{n-2}b^2 + \cdots + \binom{n}{r}a^{n-r}b^r + \cdots + b^n,$$

where n is a positive integer and $\binom{n}{r} = \frac{n!}{(n-r)!\,r!} = \frac{n(n-1)\ldots(n-r+1)}{r!}$

2. TRIGONOMETRY

Identities

$$\sin^2 A + \cos^2 A = 1.$$
$$\sec^2 A = 1 + \tan^2 A.$$
$$\operatorname{cosec}^2 A = 1 + \cot^2 A.$$
$$\sin(A \pm B) = \sin A \cos B \pm \cos A \sin B$$
$$\cos(A \pm B) = \cos A \cos B \mp \sin A \sin B$$
$$\tan(A \pm B) = \frac{\tan A \pm \tan B}{1 \mp \tan A \tan B}$$
$$\sin 2A = 2 \sin A \cos A$$
$$\cos 2A = \cos^2 A - \sin^2 A = 2\cos^2 A - 1 = 1 - 2\sin^2 A$$
$$\tan 2A = \frac{2\tan A}{1 - \tan^2 A}$$

Formulae for ΔABC

$$\frac{a}{\sin A} = \frac{b}{\sin B} = \frac{c}{\sin C}$$

$$a^2 = b^2 + c^2 - 2bc\cos A$$

$$\Delta = \frac{1}{2}ab\sin C$$

PartnerInlearning
374
www.testpapersfree.com

Downloaded from SingaKids.com

Answer all questions

1 **(i)** Differentiate $x\cos 2x$ with respect to x. [3]

(ii) Using your answer to part **(i)**, find $\int_{\pi}^{2\pi} x\sin 2x dx$. [5]

PartnerInlearning
375
www.testpapersfree.com

Downloaded from SingaKids.com

2 **(i)** Express $\frac{4x^3+5x^2+x-1}{x^2(x+1)}$ in partial fractions. [5]

(ii) Hence, find $\int \frac{4x^3+5x^2+x-1}{x^2(x+1)}dx$. [3]

PartnerInlearning
376
www.testpapersfree.com

Downloaded from SingaKids.com

3 It is given that $4^{2x+3} = 7^{3-x}$.

(i) Without using logarithms, find the exact value of 112^x. [3]

(ii) Hence use your results in (i), solve $4^{2x+3} = 7^{3-x}$, giving your answer correct to 2 decimal places. [2]

PartnerInlearning
377
www.testpapersfree.com

Downloaded from SingaKids.com

4 The equation of a curve is $y = (p+2)x^2 - 10x + 2p + 1$, where p is a constant.

(i) In the case where $p = 2$, find the set of values of x for which the curve lies above the line $y = 1$. [3]

PartnerInlearning
378
www.testpapersfree.com

Downloaded from SingaKids.com

4 **(ii)** Find the range of values of p for which the curve lies completely below the line $y = 2x + 3$. [6]

PartnerInlearning
379
www.testpapersfree.com

Downloaded from SingaKids.com

5 Solve the equation $\log_{16}(3x-16)-\log_4(2x)=5\log_4(0.5)^{0.5}$. [5]

PartnerInlearning
380
www.testpapersfree.com

Downloaded from SingaKids.com


6 **(i)** Factorise $(2 + x)^3 - 216$ completely. [2]

(ii) Hence show that $(2 + x)^3 - 216 = (x - 4)^2$ has exactly one real root. [4]

PartnerInlearning
381
www.testpapersfree.com

Downloaded from SingaKids.com

7 The diagram shows part of the curve $y = \sqrt{1+3x}$, intersecting the y-axis at A. The tangent to the curve at the point $P(5, 4)$ intersects the y-axis at B.



(i) Find the coordinates of A and of B. [4]

PartnerInlearning
382
www.testpapersfree.com


Downloaded from SingaKids.com

7 **(ii)** Calculate the area of the shaded region ABP. [4]

PartnerInlearning
383
www.testpapersfree.com

Downloaded from SingaKids.com

8 The diagram shows two points A (–6, 2) and B (10, 2) on the circumference of a circle whose centre, C, lies above the x-axis. The line $x = -8$ is a tangent to the circle.



(i) Show that the radius of the circle is 10 units. [3]

PartnerInlearning
384
www.testpapersfree.com

Downloaded from SingaKids.com

8 **(ii)** Find the equation of the circle. [4]

(iii) Find the equations of the tangents to the circle parallel to the x-axis. [2]

PartnerInlearning
385
www.testpapersfree.com

Downloaded from SingaKids.com

9 The equation of the curve is $y = \frac{e^{2x}}{3+4x}$.

(i) Find the coordinates of the stationary point on the curve, leaving your answer in exact value. [4]

(ii) Determine the nature of this stationary point. [2]

PartnerInlearning
386
www.testpapersfree.com

Downloaded from SingaKids.com

10 In order for $y = h(1+x)^k$, where h and k are unknown constants to be represented by a straight line graph, it needs to be expressed in the form $Y = mX + c$, where X and Y are functions of x and/or y, and m and c are constants.

(i) Determine an expression for Y and for X. [2]

(ii) Explain how the straight line may be used to determine the value of h. [1]

PartnerInlearning
387
www.testpapersfree.com

Downloaded from SingaKids.com

11 The variables x and y are known to be related by an equation of the form

$\frac{x+2}{a}+\frac{y^2}{b}=1$, where a and b are constants.

Experimental values of x and y are shown in the following table.

One of the values of y is subject to an abnormally large error.

x	1	2	3	4	5
y	2.65	3.00	3.32	3.71	3.87


(i) On the grid on page 17, draw the graph of y^2 against $x + 2$. [3]

(ii) Use the graph to identify the coordinates for the abnormal reading in the table above and estimate its correct y -value. [2]

(iii) Use the graph to estimate the value of a and b. [3]

PartnerInlearning
388
www.testpapersfree.com


Downloaded from SingaKids.com



PartnerInlearning
389
www.testpapersfree.com

Downloaded from SingaKids.com

12 The diagram shows a rock climbing wall. The wall AB, of length 20 m, is to be inclined at an angle θ from the vertical while the wall BC, of length 9 m, is to be inclined at the same angle θ from the horizontal. The height of the whole wall is H m.



(i) Show that $H = 20\cos\theta + 9\sin\theta$. [2]

PartnerInlearning
390
www.testpapersfree.com
Downloaded from SingaKids.com

12 **(ii)** Express H in the form $R\sin(\theta+\alpha)$, where $R>0$ and $0°<\alpha<90°$. [4]

(iii) Find the greatest possible value of H and the value of θ at which this occurs. [3]

PartnerInlearning
391
www.testpapersfree.com

Downloaded from SingaKids.com

13 The gradient function of a curve y is given by $2x^2 + x - 6$. [6]

Given that y has a minimum value of $1\frac{3}{8}$, find the equation of the curve.

End of Paper

PartnerInlearning
392
www.testpapersfree.com

Downloaded from SingaKids.com

www.testpapersfree.com

Downloaded from SingaKids.com

Answer Key

1i	$-2x\sin 2x+\cos 2x$	7i	$A(0,\ 1),\ B(0,\frac{17}{8})$
1ii	$-\frac{\pi}{2}$	7ii	$1\frac{5}{16} or 1.3125 units^2$
2i	$4+\frac{2}{x}-\frac{1}{x^2}-\frac{1}{x+1}$	8ii	$(x-2)^2+(y-8)^2=100$
2ii	$4x+2\ln x+\frac{1}{x}-\ln(x+1)+c$	8iii	$y=18$ $y=-2$
3i	$112^x=\frac{343}{64}$	9i	$\left(-\frac{1}{4},\frac{1}{2\sqrt{e}}\right)$
3ii	0.36	9ii	Minimum point
4i	$x<\frac{1}{2}$ or $x>2$	10i	$Y=\lg y, X=\lg(1+x)$
4ii	$p<-2$ and $p<-5$ or $p>4$ $\therefore p<-5$	10ii	$h=10^{vertical\ intercept}$ or $h=e^{vertical\ intercept}$
5	$x=8$ or $x=16$	11ii	Abnormal reading (4, 3.71) Estimated value of $y^2=13$ Estimated value of $y=3.61$
		11iii	$a=-0.551, b=1.1$
6i	$(x-4)(x^2+10x+52)$		
6ii	$x=4$ or $x=\frac{-9\pm\sqrt{9^2-4(1)(56)}}{2(1)}$ $x=\frac{-9\pm\sqrt{-143}}{2}$ (no soln) Therefore, there is only one real root.	12ii 12iii	$H=\sqrt{481}\sin(\theta+65.8°)$ Greatest value = $\sqrt{481}$ or 21.9 $\theta=24.2°$
		13	$y=\frac{2x^3}{3}+\frac{x^2}{2}-6x+7$

PartnerInlearning
394
www.testpapersfree.com

Downloaded from SingaKids.com

1 Do not use a calculator in this question.

(a) Given that A and B are acute angles such that $\sin(A-B)=\frac{3}{8}$ and $\sin A\cos B=\frac{5}{8}$, find the value of

(i) $\cos A\sin B$, [2]

$$\sin(A-B)=\frac{3}{8}$$

$\sin A\cos B-\cos A\sin B=\frac{3}{8}$ [M1 - applying compound angle formula]

$\frac{5}{8}-\cos A\sin B=\frac{3}{8}$

$\cos A\sin B=\frac{1}{4}$ [A1 - $\frac{1}{4}$ or 0.25 only]

(ii) $\cot A\tan B$. [2]

$\cot A\tan B=\frac{\cos A}{\sin A}\times\frac{\sin B}{\cos B}$ [B1 - express $\cot A$ or $\tan B$ in sine and cosine]

$=\frac{\cos A\sin B}{\sin A\cos B}$

$=\frac{\frac{1}{4}}{\frac{5}{8}}$

$=\frac{2}{5}$ [A1]

PartnerInlearning
395
www.testpapersfree.com

Downloaded from SingaKids.com

1 (b) Given that $\tan A = -\frac{3}{4}$ and $\cos B = \frac{5}{13}$, where A is an obtuse angle and B is a reflex angle, find

(i) $\cos 2A$, [2]

$\cos 2A = 1 - 2\sin^2 A$

$= 1 - 2\left(\frac{3}{5}\right)^2$ [B1 - value of $\sin A$]

$= \frac{7}{25}$ [A1]

Alternative Solution:

$\cos 2A = 2\cos^2 A - 1$

$= 2\left(-\frac{4}{5}\right)^2 - 1$ [B1 - value of $\cos A$]

$= \frac{7}{25}$ [A1]

(ii) $\tan(A-B)$. [2]

$\tan(A-B) = \frac{\tan A - \tan B}{1 + \tan A \tan B}$

$= \frac{-\frac{3}{4} - \left(-\frac{12}{5}\right)}{1 + \left(-\frac{3}{4}\right)\left(-\frac{12}{5}\right)}$ [B1 - value of $\tan B$ s.o.i.]

$= \frac{33}{56}$ [A1]

PartnerInlearning
396
www.testpapersfree.com
Downloaded from SingaKids.com

2 Given that $\sqrt{p+q\sqrt{8}} = \dfrac{9}{4-\sqrt{8}}$, where p and q are rational numbers, find the values of p and q. [4]

$$\sqrt{p+q\sqrt{8}} = \frac{9}{4-\sqrt{8}}$$

$$p+q\sqrt{8} = \left(\frac{9}{4-\sqrt{8}}\right)^2$$

$$= \frac{81}{24-8\sqrt{8}} \quad \text{[B1 - for } 24-8\sqrt{8}\text{]}$$

$$= \frac{81}{24-8\sqrt{8}} \times \frac{24+8\sqrt{8}}{24+8\sqrt{8}} \quad \text{[M1 - conjugate of their den.]}$$

$$= \frac{81\left(24+8\sqrt{8}\right)}{64}$$

$$= \frac{243}{8} + \frac{81}{8}\sqrt{8} \quad \text{[A1]}$$

$$p = \frac{243}{8} \qquad q = \frac{81}{8} \quad \text{[A1]}$$

PartnerInlearning
397
www.testpapersfree.com
Downloaded from SingaKids.com

3 Baking powder is poured onto a flat surface at a constant rate of 2π cm^{3}s^{-1} and formed a right circular cone. The radius of the cone is always $\frac{1}{18}$ of its height. Find the rate of change of the radius of the cone after 3 seconds of pouring. [5]

Vol. of cone, $V = \frac{1}{3}\pi r^2(18r)$

$= 6\pi r^3$

$\frac{dV}{dr} = 18\pi r^2$ [B1]

After 3 seconds, $V = 6\pi$

$6\pi r^3 = 6\pi$ [M1 - finding corresponding r]

$r = 1$ [A1]

$\frac{dV}{dt} = \left.\frac{dV}{dr}\right|_{r=1} \times \left.\frac{dr}{dt}\right|_{r=1}$ [M1 - connected rate of change]

$2\pi = 18\pi(1)^2 \times \left.\frac{dr}{dt}\right|_{r=1}$

$\left.\frac{dr}{dt}\right|_{r=1} = \frac{1}{9}$

The rate of change required is $= \frac{1}{9}$ cm/s. [A1 o.e.]

PartnerInlearning
398
www.testpapersfree.com
Downloaded from SingaKids.com

4 (a) The quantity, N, of a micro-organism multiply themselves under ideal conditions based on the formula $N = N_0 e^{\frac{t}{7}}$ where N_0 is a constant and t is the time interval in minutes.

Find the time taken for the quantity of the micro-organism to be twice of the initial quantity. [3]

When $N = 2N_0$,

$2N_0 = N_0 e^{\frac{t}{7}}$ [M1]

$2 = e^{\frac{t}{7}}$

$\frac{t}{7} = \ln 2$ [M1]

$t = 7\ln 2$ [A1]

The time taken $= 4.85$ minutes (3 sf)

(b) In order to obtain a graphical solution for the equation $x = -2\log_9(3-x)$, a straight line graph has to be drawn on the graph of $y = 3^{-x}$.

Find the equation of the straight line that need to be drawn. [3]

$x = -2\log_9(3-x)$

$-\frac{x}{2} = \log_9(3-x)$

$9^{-\frac{x}{2}} = 3-x$ [M1 - converting log to exp form]

$3^{-x} = 3-x$ [M1 - getting 3^{-x} as the subject]

Equation of line: $y = 3-x$ [A1]

PartnerInlearning
399
www.testpapersfree.com
Downloaded from SingaKids.com

5 The roots of a cubic equation $F(x)=0$ are -1, 2 and 5. When $F(x)$ is divided by $x-3$, the remainder is 30.

(i) Find the remainder when $F(x)$ is divided by $x+3$. [4]

$F(x)=k(x+1)(x-2)(x-5)$ [M1 - factor form with coeff of x^3 is k]

$F(3)=k(3+1)(3-2)(3-5)$ [M1 - apply Remainder Theorem]

$30=-8k$

$k=-\frac{15}{4}$ [A1]

$F(x)=-\frac{15}{4}(x+1)(x-2)(x-5)$

$F(-3)=-\frac{15}{4}(-3+1)(-3-2)(-3-5)$

$=300$ [A1]

The remainder $=300$

(ii) Solve the equation $F\left(\sqrt{x}\right)=0$. [2]


$F(\sqrt{m})=0$

$-\frac{15}{4}\left(\sqrt{m}+1\right)\left(\sqrt{m}-2\right)\left(\sqrt{m}-5\right)=0$ [M1 - Replacing x with $\sqrt{m}$]

$m=4$ or $m=25$ [A1]

PartnerInlearning
400
www.testpapersfree.com
Downloaded from SingaKids.com

6 (a) The graph below shows part of a trigonometric function.



(i) State the amplitude and period of the function. [2]


Amplitude = 4.5	[B1]
Period = $\frac{2\pi}{3}$	[B1]

(ii) Explain why the graph cannot represent the tangent function. [1]

Any acceptable reasons: [B1]
Because the graph is continuous.
Because the graph has maximum and minimum.
Because the graph does not have asymptote lines.

PartnerInlearning
401
www.testpapersfree.com
Downloaded from SingaKids.com

6 (b) (i) Sketch the graph of $y = -4\sin 3x + 2$ for $0° \le x \le 360°$. [3]



[B1 – shape starting from $y = 2$] [B1 – 3 cyles] [B1 – amplitude]

(ii) State the number of solutions for the equation $5 = -4\sin 6x + 2$ for $0° \le x \le 360°$. [1]

There are 12 solutions. [B1]

PartnerInlearning
402
www.testpapersfree.com
Downloaded from SingaKids.com

7 A curve has the equation $y = f(x)$, where $f(x) = \dfrac{5x+11}{x^2+3}$.

(i) Find the equation of normal to the curve at the point where the curve passes through the y-axis. [6]

When $x = 0$,

$$y = \frac{11}{3} \quad [B1]$$

$$f'(x) = \frac{5\left(x^2+3\right)-(5x+11)(2x)}{\left(x^2+3\right)^2} \quad [B2]$$

$$= \frac{-5x^2-22x+15}{\left(x^2+3\right)^2}$$

$$f'(0) = \frac{5}{3} \quad [A1\checkmark]$$

$$\text{gradient of normal} = -\frac{3}{5} \quad [A1\checkmark]$$

Equation of normal:

$$y = -\frac{3}{5}x + \frac{11}{3} \quad [A1]$$

(ii) Determine the range of values of x for which $f(x)$ is a decreasing function. [3]

$f'(x) < 0$ [M1]

$-5x^2 - 22x + 15 < 0$ [M1]

$(-5x+3)(x+5) < 0$

$x < -5$ or $x > \dfrac{3}{5}$ [A1]

PartnerInlearning
403
www.testpapersfree.com

Downloaded from SingaKids.com

8 (i) Prove the identity $\frac{\sin 2x}{\sin x} - \frac{\cos 2x}{\cos x} = \sec x$. [3]

$$\text{LHS} = \frac{\sin 2x}{\sin x} - \frac{2\cos^2 x - 1}{\cos x}$$

$$= \frac{2\sin x \cos x}{\sin x} - \frac{2\cos^2 x}{\cos x} + \frac{1}{\cos x}$$ [B1 - either double angle formula applied] [M1 - splitting into 2 fractions]

$$= 2\cos x - 2\cos x + \sec x$$ [B1 - $\frac{1}{\cos x}$ to $\sec x$ seen]

$$= \sec x$$

$$= \text{RHS}$$

Alternative Solution:

$$\text{LHS} = \frac{\sin 2x}{\sin x} - \frac{2\cos^2 x - 1}{\cos x}$$

$$= \frac{2\sin x \cos x}{\sin x} - \frac{2\cos^2 x - 1}{\cos x}$$ [B1 - double angle formula]

$$= \frac{2\sin x \cos^2 x - \sin x\left(2\cos^2 x - 1\right)}{\sin x \cos x}$$ [M1 - combine into single fraction]

$$= \frac{2\sin x \cos^2 x - 2\sin x \cos^2 x + \sin x}{\sin x \cos x}$$

$$= \frac{\sin x}{\sin x \cos x}$$

$$= \frac{1}{\cos x}$$ [B1 - $\frac{1}{\cos x}$ to $\sec x$ seen]

$$= \sec x$$

$$= \text{RHS}$$

(ii) Solve the equation $\frac{2\sin 2x}{\sin x} - \frac{2\cos 2x}{\cos x} = 3\cos x + 1$ for $0° < x < 360°$. [4]

$2\sec x = 3\cos x + 1$ [B1 - LHS to $2\sec x$]

$0 = 3\cos^2 x + \cos x - 2$ [M1 - forming quad. eqn. in cosine]

$0 = (3\cos x - 2)(\cos x + 1)$

$\cos x = \frac{2}{3}$ or $\cos x = -1$

$x = 48.2°, 311.8°$ or $x = 180°$ (rej.) [A1] [A1]

PartnerInlearning
404
www.testpapersfree.com

Downloaded from SingaKids.com

9 A particle travels in a straight line so that t seconds after passing a fixed point O with a velocity of 15 cms^{-1}, its acceleration a cms^{-2} is given by $a = k - 2t$ where k is a constant. The particle reaches maximum velocity in 1 second.

Find

(i) the value of k, [1]

When $t = 1, a = 0$:

$0 = k - 2(1)$

$k = 2$ [B1]

(ii) an expression for the velocity, v, in terms of t, [3]

$v = \int a \, dt$ [M1 - obtain v from integrating a]

$= 2t - t^2 + c$ [B1 - without the c]

When $t = 0, v = 15$:

$c = 15$

$v = -t^2 + 2t + 15$ [A1]

(iii) the distance travelled in the first 10 seconds. [4]

$s = -\frac{1}{3}t^3 + t^2 + 15t + d$ [M1 - integrating v to get s]

When $t = 0, s = 0$:

$d = 0$ [A1]

When $v = 0$ [M1 - find t when v is 0]

$-t^2 + 2t + 15 = 0$

$(-t + 5)(t + 3) = 0$

$t = 5$ or $t = -3$

When $t = 0$, $s = 0$

When $t = 5$, $s = \frac{175}{3}$ [M1 - find s when t is 5 and t is 10]

When $t = 10$, $s = -\frac{250}{3}$

distance travelled $= \frac{175}{3} \times 2 + \frac{250}{3} = 200$ cm [A1]

PartnerInlearning
405
www.testpapersfree.com

Downloaded from SingaKids.com

10 $f(x)$ is such that $f'(x) = -2\sin 4x + \cos 3x$.

Given that $f(0) = 0$, find the exact value of $f\left(\frac{\pi}{4}\right)$. [6]

$f'(x) = -2\sin 4x + \cos 3x$

$f(x) = \int -2\sin 4x + \cos 3x \, dx$ [M1 - attempt to integrate]

$= \frac{1}{2}\cos 4x + \frac{1}{3}\sin 3x + c$ [B1 - for $\frac{1}{2}\cos 4x$]

[B1 - for $\frac{1}{3}\sin 3x$]

$f(0) = \frac{1}{2}\cos 0 + \frac{1}{3}\sin 0 + c$

$0 = \frac{1}{2} + c$

$c = -\frac{1}{2}$ [A1]

$f(x) = \frac{1}{2}\cos 4x + \frac{1}{3}\sin 3x - \frac{1}{2}$


$f\left(\frac{\pi}{4}\right) = \frac{1}{2}\cos\left(\frac{4\pi}{4}\right) + \frac{1}{3}\sin\left(\frac{3\pi}{4}\right) - \frac{1}{2}$

$= \frac{1}{2}(-1) + \frac{1}{3}\left(\frac{1}{2}\sqrt{2}\right) - \frac{1}{2}$ [B1 - $\frac{1}{2}\sqrt{2}$ s.o.i.]

$= \frac{1}{6}\sqrt{2} - 1$ [A1 o.e.]

PartnerInlearning
406
www.testpapersfree.com
Downloaded from SingaKids.com

11 The diagram shows a triangle PQR circumscribed in a circle.
$PQ = 10$ cm , $QR = x$ cm and PR is the diameter of the circle.



(i) Explain why the area of shaded regions, A cm^2, is $25\pi + \frac{\pi}{4}x^2 - 5x$. [4]

angle $PQR = 90°$ (angle in semicircle) [B1]

By Pytagoras' Theorem,

$PR^2 = 10^2 + x^2$ [M1]

$A = \pi\left(\frac{1}{4}\right)PR^2 - \frac{1}{2}(10)(x)$ [M1]
[B1 - expression for radius]

$= \frac{\pi}{4}\left(100 + x^2\right) - 5x$

$= 25\pi + \frac{\pi}{4}x^2 - 5x$ [AG]

(ii) Given that x can vary, find the minimum area of the shaded region. [3]

$\frac{dA}{dr} = 0$ [M1]

$\frac{\pi}{2}x - 5 = 0$ [B1 - correct differentiation]

$x = \frac{10}{\pi}$

$\therefore A = 25\pi + \frac{\pi}{4}\left(\frac{10}{\pi}\right)^2 - 5\left(\frac{10}{\pi}\right)$

$= 70.6$ cm^2 [A1 - can be simplified in terms of π]

$= 25\pi - \frac{25}{\pi}$ cm^2

PartnerInlearning
407
www.testpapersfree.com
Downloaded from SingaKids.com

12 Given that the expansion of $\left(1+\frac{x}{2}\right)^n(3-2x)$ up to the first three terms, in ascending powers of x, is $h+10x+kx^2$, find the values of h, k and n. [7]

$$\left(1+\frac{x}{2}\right)^n(3-2x)=\left(1+\binom{n}{1}\left(\frac{x}{2}\right)+\binom{n}{2}\left(\frac{x}{2}\right)^2+\ldots\right)(3-2x) \quad \text{[M1]}$$

$$=\left(1+\frac{1}{2}nx+\frac{1}{8}n(n-1)x^2+\ldots\right)(3-2x) \quad \left[\text{B1 - } \binom{n}{1}=n \text{ or } \binom{n}{2}=\frac{n(n-1)}{2}\right]$$

Comparing coefficient of x^0 :

$$h=3 \quad \text{[A1]}$$

Comparing coefficient of x^1 :

$$\frac{3}{2}n-2=10 \quad \text{[M1]}$$

$$n=8 \quad \text{[A1]}$$

Comparing coefficient of x^2 :


$$\frac{3}{8}n(n-1)-n=k \quad \text{[M1]}$$

$$k=\frac{3}{8}(8)(8-1)-8$$

$$=13 \quad \text{[A1]}$$

PartnerInlearning
408
www.testpapersfree.com
Downloaded from SingaKids.com

13 The diagram below shows a trapezium $OABC$, where O is the origin.



The equation of AO is $y = 4x$ and the equation of OC is $y + 3x = 0$.
The line through A perpendicular to OA meets y-axis at B and BC is parallel to AO.

Given that the length of OA is $\sqrt{1700}$ units, find the coordinates of A, of B and of C. [10]

$A(x_A, 4x_A)$ [B1]

$\sqrt{(x_A - 0)^2 + (4x_A - 0)^2} = \sqrt{1700}$ [M1 - distance of coords.]

$17x_A^2 = 1700$

$x_A = 10$

$\therefore A(10, 40)$ [A1]

$B(0, y_B)$ [B1]

gradient of $AB = -\frac{1}{4}$ [B1]

$\frac{y_B - 40}{0 - 10} = -\frac{1}{4}$ [M1]

$y_B = 42.5$

$\therefore B(0, 42.5)$ [A1]

$C(x_C, -3x_C)$ [B1]

gradient of $CB = 4$ [B1]

$\frac{42.5 - (-3x_C)}{0 - x_C} = 4$

$x_C = -\frac{85}{14}$

$\therefore C\left(-\frac{85}{14}, \frac{255}{14}\right)$ [A1]

~~~ ***End of Paper*** ~~~

PartnerInlearning
409
www.testpapersfree.com

Downloaded from SingaKids.com
~~~

ZHONGHUA SECONDARY SCHOOL
PRELIMINARY EXAMINATION 2021
SECONDARY 4 EXPRESS

Candidate's Name	Class	Register Number
Marking Scheme		

ADDITIONAL MATHEMATICS

4049/02

PAPER 2

14 September 2021
2 hours 15 minutes

Candidates answer on the Question Paper

READ THESE INSTRUCTIONS FIRST

Write your name, class and register number on all the work you hand in.
Write in dark blue or black pen on both sides of the paper.
You may use an HB pencil for any diagrams or graphs.
Do not use staples, paper clips, glue or correction fluid.

Answer **all** the questions.
Give non-exact numerical answers correct to 3 significant figures, or 1 decimal place in the case of angles in degrees, unless a different level of accuracy is specified in the question.
The use of a scientific calculator is expected, where appropriate.
You are reminded of the need for clear presentation in your answers.

The number of marks is given in brackets [ ] at the end of each question or part question.
The total number of marks for this paper is **90**.

For Examiner's Use
90

Setter: Ms Lee SK
Vetted by: Mr Poh WB

This question paper consists of **20** printed pages (including this cover page)

PartnerInlearning
410
www.testpapersfree.com

Downloaded from SingaKids.com

Mathematical Formulae

1. ALGEBRA

Quadratic Equation

For the equation $ax^2 + bx + c = 0$,

$$x = \frac{-b \pm \sqrt{b^2 - 4ac}}{2a}$$

Binomial Theorem

$$(a+b)^n = a^n + \binom{n}{1}a^{n-1}b + \binom{n}{2}a^{n-2}b^2 + \cdots + \binom{n}{r}a^{n-r}b^r + \cdots + b^n,$$

where n is a positive integer and $\binom{n}{r} = \frac{n!}{(n-r)!\,r!} = \frac{n(n-1)\ldots(n-r+1)}{r!}$

2. TRIGONOMETRY

Identities

$$\sin^2 A + \cos^2 A = 1.$$
$$\sec^2 A = 1 + \tan^2 A.$$
$$\operatorname{cosec}^2 A = 1 + \cot^2 A.$$
$$\sin(A \pm B) = \sin A \cos B \pm \cos A \sin B$$
$$\cos(A \pm B) = \cos A \cos B \mp \sin A \sin B$$
$$\tan(A \pm B) = \frac{\tan A \pm \tan B}{1 \mp \tan A \tan B}$$
$$\sin 2A = 2 \sin A \cos A$$
$$\cos 2A = \cos^2 A - \sin^2 A = 2\cos^2 A - 1 = 1 - 2\sin^2 A$$
$$\tan 2A = \frac{2\tan A}{1 - \tan^2 A}$$

Formulae for ΔABC

$$\frac{a}{\sin A} = \frac{b}{\sin B} = \frac{c}{\sin C}$$

$$a^2 = b^2 + c^2 - 2bc\cos A$$

$$\Delta = \frac{1}{2}ab\sin C$$

PartnerInlearning
411
www.testpapersfree.com

Downloaded from SingaKids.com

Answer all questions

1 **(i)** Differentiate $x\cos 2x$ with respect to x. [3]

$$\frac{d}{dx}(x\cos 2x)$$
$$= x(-2\sin 2x) + cos2x$$
$$= -2x\sin 2x + \cos 2x$$

[B1] $-2\sin 2x$
[M1] product rule
[A1]

(ii) Using your answer to part **(i)**, find $\int_{\pi}^{2\pi} x\sin 2x dx$. [5]

$$\int_{\pi}^{2\pi}(-2x\sin 2x + \cos 2x)dx = \left[x\cos 2x\right]_{\pi}^{2\pi}$$

[M1] reverse differentiation

$$\int_{\pi}^{2\pi}(-2x\sin 2x)dx = -\int_{\pi}^{2\pi}\cos 2x dx + \left[x\cos 2x\right]_{\pi}^{2\pi}$$

$$\int_{\pi}^{2\pi}(x\sin 2x)dx = \frac{1}{2}\left[\frac{1}{2}\sin 2x\right]_{\pi}^{2\pi} - \frac{1}{2}\left[x\cos 2x\right]_{\pi}^{2\pi}$$

[B1] $\frac{1}{2}\sin 2x$,
[A1] FT $\div\left(-\frac{1}{2}\right)$

$$\int_{\pi}^{2\pi}(x\sin 2x)dx = \frac{1}{4}\left[\sin 4\pi - \sin 2\pi\right] - \frac{1}{2}\left[2\pi\cos 4\pi - \pi\cos 2\pi\right]$$

[M1] sub in 2π, π

$$\int_{\pi}^{2\pi}(x\sin 2x)dx = \frac{1}{4}\left[0-0\right] - \frac{1}{2}\left[2\pi - \pi\right]$$

$$\int_{\pi}^{2\pi}(x\sin 2x)dx = -\frac{\pi}{2}$$

[A1]

PartnerInlearning
412
www.testpapersfree.com

Downloaded from SingaKids.com

2 **(i)** Express $\dfrac{4x^3+5x^2+x-1}{x^2(x+1)}$ in partial fractions. [5]

$\dfrac{4x^3+5x^2+x-1}{x^2(x+1)} = 4+\dfrac{x^2+x-1}{x^2(x+1)}$ [M1] long division

$\dfrac{x^2+x-1}{x^2(x+1)} = \dfrac{A}{x}+\dfrac{B}{x^2}+\dfrac{C}{x+1}$ [B1]

$x^2+x-1 = Ax(x+1)+B(x+1)+Cx^2$ [M1] remove denominator

When $x = 0$, $-1 = B$

When $x = -1$, $1-1-1 = C$
$C = -1$

When $x = 1$, $1 = 2A-(1+1)-1$
$1 = 2A-3$
$2A = 4$
$A = 2$

$4+\dfrac{2}{x}-\dfrac{1}{x^2}-\dfrac{1}{x+1}$

[A2] all correct
[A1] 1 wrong
[A0] 2 or more wrong

(ii) Hence, find $\int \dfrac{4x^3+5x^2+x-1}{x^2(x+1)}dx$. [3]

$\int \dfrac{4x^3+5x^2+x-1}{x^2(x+1)}dx$

$= \int\left(4+\dfrac{2}{x}-\dfrac{1}{x^2}-\dfrac{1}{x+1}\right)dx$ [M1] FT

$= 4x+2\ln x+\dfrac{1}{x}-\ln(x+1)+c$ [B1], [B1] for any of the terms except $4x$

PartnerInlearning
413
www.testpapersfree.com

Downloaded from SingaKids.com

3 It is given that $4^{2x+3} = 7^{3-x}$.

(i) Without using logarithms, find the exact value of 112^x. [3]

$4^{2x+3} = 7^{3-x}$

$4^{2x} \times 4^3 = 7^3 \times 7^{-x}$ [B1] split up of powers

$16^x \times 64 = 343 \times 7^{-x}$

$16^x \div 7^{-x} = \frac{343}{64}$

$16^x \times 7^x = \frac{343}{64}$ [M1]

$(16 \times 7)^x = \frac{343}{64}$

$112^x = \frac{343}{64}$ [A1] accept mixed fraction

(ii) Hence use your results in (i), solve $4^{2x+3} = 7^{3-x}$, giving your answer correct to 2 decimal places. [2]

$112^x = \frac{343}{64}$

$x \lg 112 = \lg \frac{343}{64}$ [M1] lg or ln both sides

$x = \lg \frac{343}{64} \div \lg 112$

$x = 0.3558$

$x = 0.36$ (2 d.p.) [A1]

PartnerInlearning
414
www.testpapersfree.com

Downloaded from SingaKids.com

4 The equation of a curve is $y=(p+2)x^2-10x+2p+1$, where p is a constant.

(i) In the case where $p=2$, find the set of values of x for which the curve lies above the line $y=1$. [3]


When $p=2$,

$4x^2-10x+5>1$ [M1] inequality

$4x^2-10x+4>0$

$2x^2-5x+2>0$

$(2x-1)(x-2)>0$ [A1] critical values



$x<\frac{1}{2}$ or $x>2$ [A1]

4 **(ii)** Find the range of values of p for which the curve lies completely below the line $y=2x+3$. [6]

$(p+2)x^2-10x+2p+1<2x+3$ [M1] Eqn or inequality

$(p+2)x^2-12x+2p-2<0$

$p+2<0$ and $b^2-4ac<0$ [B1] $p<-2$

$p<-2$ and $(-12)^2-4(p+2)(2p-2)<0$ [M1] with sub and <0


$144-4(2p^2+2p-4)<0$

$144-8p^2-8p+16<0$

$-8p^2-8p+160<0$

$p^2+p-20>0$

$(p-4)(p+5)>0$ [M1] critical values



$p<-2$ and $p<-5$ or $p>4$ [A1]

$\therefore p<-5$ [A1]

PartnerInlearning
415
www.testpapersfree.com

Downloaded from SingaKids.com

5 Solve the equation $\log_{16}(3x-16)-\log_4(2x)=5\log_4(0.5)^{0.5}$. [5]

$\log_{16}(3x-16)-\log_4(2x)=5\log_4(0.5)^{0.5}$

$\frac{\log_4(3x-16)}{\log_4 16}-\log_4(2x)=\log_4(0.5)^{2.5}$ [M1] change to same base

$\frac{1}{2}\log_4(3x-16)-\log_4(2x)=\log_4(2)^{-2.5}$

$\log_4(3x-16)-2\log_4(2x)=2\log_4(2)^{-2.5}$

$\log_4\left(\frac{3x-16}{4x^2}\right)=\log_4(2)^{-5}$ [M1] any correct law of log

$\frac{3x-16}{4x^2}=\frac{1}{32}$ [M1] remove log

$3x-16=\frac{x^2}{8}$

$24x-128=x^2$

$x^2-24x+128=0$ [B1] equivalent eqn

$(x-8)(x-16)=0$

$x=8$ or $x=16$ [A1] check factors

6 **(i)** Factorise $(2+x)^3-216$ completely. [2]

$(2+x)^3-216$

$=(2+x)^3-6^3$

$=(2+x-6)[(2+x)^2+(2+x)(6)+6^2]$ [M1]

$=(x-4)(4+4x+x^2+12+6x+36)$

$=(x-4)(x^2+10x+52)$ [A1]

(ii) Hence show that $(2+x)^3-216=(x-4)^2$ has exactly one real root. [4]

$(2+x)^3-216=(x-4)^2$

$(x-4)(x^2+10x+52)=(x-4)^2$ [M1]

$(x-4)(x^2+10x+52)-(x-4)^2=0$

$(x-4)[x^2+10x+52-x+4]=0$ [M1]

$(x-4)(x^2+9x+56)=0$

$x=4$ or $x=\frac{-9\pm\sqrt{9^2-4(1)(56)}}{2(1)}$ [M1]


$x=\frac{-9\pm\sqrt{-143}}{2}$ (no soln) [A1]

Therefore, there is only one real root.

PartnerInlearning
416
www.testpapersfree.com

Downloaded from SingaKids.com

7 The diagram shows part of the curve $y = \sqrt{1+3x}$, intersecting the y-axis at A. The tangent to the curve at the point $P(5, 4)$ intersects the y-axis at B.



(i) Find the coordinates of A and of B. [4]

$y = \sqrt{1+3x}$
Sub $x = 0, y = 1$
$A(0, 1)$ [B1]

$\frac{dy}{dx}$
$= \frac{1}{2}(1+3x)^{-\frac{1}{2}}(3)$ [M1] correct chain rule
$= \frac{3}{2\sqrt{1+3x}}$

When $x = 5$,
Gradient
$= \frac{dy}{dx}$
$= \frac{3}{2\sqrt{1+3(5)}}$
$= \frac{3}{8}$ [B1]

Equation of tangent at P:
$y - 4 = \frac{3}{8}(x-5)$
$y = \frac{3}{8}x + \frac{17}{8}$
$B(0, \frac{17}{8})$ [A1]

PartnerInlearning
417
www.testpapersfree.com
Downloaded from SingaKids.com

7 **(ii)** Calculate the area of the shaded region ABP. [4]

Area

$= \int_0^5 \left[\frac{3}{8}x + \frac{17}{8} - (1+3x)^{1/2}\right] dx$ [M1] line – curve


$= \left[\frac{3}{8}\left(\frac{x^2}{2}\right) + \frac{17}{8}x - \frac{(1+3x)^{3/2}}{3(3/2)}\right]_0^5$ [M1] integration of line
[M1] integration of curve

$= \left[\frac{3}{8}\left(\frac{25}{2}\right) + \frac{17}{8}(5)\right] - \left[\frac{2(1+15)^{3/2}}{9} - \frac{2}{9}(1)\right]$

$= \frac{245}{16} - 14$

$= 1\frac{5}{16} \text{ or } 1.3125 \text{ units}^2$ [A1]

8 The diagram shows two points A (–6, 2) and B (10, 2) on the circumference of a circle whose centre, C, lies above the x-axis. The line $x = -8$ is a tangent to the circle.



(i) Show that the radius of the circle is 10 units. [3]

Midpoint of AB

$= \left(\frac{-6+10}{2}, \frac{2+2}{2}\right)$ [M1]

$= (2, 2)$

Centre lies on $x = 2$, [B1] s.o.i

Distance between tangent and centre
= radius

$= 8 + 2$ [A1] must be seen

= 10 units [AG]

PartnerInlearning
418
www.testpapersfree.com

Downloaded from SingaKids.com

8 **(ii)** Find the equation of the circle. [4]

$\sqrt{(2+6)^2+(y-2)^2}=10$ [M1]

$64+(y-2)^2=100$

$(y-2)^2=36$

$y-2=\pm 6$

$y=8 or -4 (rej)$ [A1]

$C(2, 8)$ [B1] s.o.i

$(x-2)^2+(y-8)^2=100$ [A1]

(iii) Find the equations of the tangents to the circle parallel to the x-axis. [2]

$y=18$ [B1]

$y=-2$ [B1]

PartnerInlearning
419
www.testpapersfree.com

Downloaded from SingaKids.com

9 The equation of the curve is $y = \frac{e^{2x}}{3+4x}$.

(i) Find the coordinates of the stationary point on the curve, leaving your answer in exact value. [4]

$\frac{dy}{dx}$

$= \frac{2e^{2x}(3+4x) - e^{2x}(4)}{(3+4x)^2}$ [B1] correct quotient rule

$= \frac{e^{2x}(6+8x-4)}{(3+4x)^2}$ [M1] factorise e^{2x}

$= \frac{e^{2x}(8x+2)}{(3+4x)^2}$

Stationary point,

$\frac{dy}{dx} = 0$ [M1] $\frac{dy}{dx} = 0$

$\frac{e^{2x}(8x+2)}{(3+4x)^2} = 0$

$e^{2x}(8x+2) = 0$

$e^{2x} > 0,\ 8x+2 = 0$

$x = -\frac{1}{4}$

$y = \frac{e^{2(-1/4)}}{3+4(-1/4)}$

$y = \frac{e^{-1/2}}{2}$

$\left(-\frac{1}{4}, \frac{1}{2\sqrt{e}}\right)$ [A1]

(ii) Determine the nature of this stationary point. [2]

x	$-\frac{1}{4}^-$	$-\frac{1}{4}$	$-\frac{1}{4}^+$
Sign of dy/dx	-ve	0	+ve

[M1] don't give if x is wrong

[A1]

Min point

PartnerInlearning
420
www.testpapersfree.com

Downloaded from SingaKids.com

10 In order for $y = h(1+x)^k$, where h and k are unknown constants to be represented by a straight line graph, it needs to be expressed in the form $Y = mX + c$, where X and Y are functions of x and/or y, and m and c are constants.

(i) Determine an expression for Y and for X. [2]

$\lg y = \lg h + \lg(1+x)^k$ Either lg or ln both sides [M1]

$\lg y = \lg h + k\lg(1+x)$

$Y = \lg y, X = \lg(1+x)$ [A1] both correct

(ii) Explain how the straight line may be used to determine the value of h. [1]

Vertical intercept
$= \lg h$

$h = 10^{vertical\ intercept}$ or $h = e^{vertical\ intercept}$ [B1]

PartnerInlearning
421
www.testpapersfree.com

Downloaded from SingaKids.com

11 The variables x and y are known to be related by an equation of the form

$\frac{x+2}{a}+\frac{y^2}{b}=1$, where a and b are constants.

Experimental values of x and y are shown in the following table.

One of the values of y is subject to an abnormally large error.

x	1	2	3	4	5
y	2.65	3.00	3.32	3.71	3.87

(i) On the grid on page 17, draw the graph of y^2 against $x + 2$. [3]

$\frac{x+2}{a}+\frac{y^2}{b}=1$

$\frac{y^2}{b}=1-\frac{x+2}{a}$

$y^2=b-\frac{b}{a}(x+2)$

$Y=y^2, X=x+2, m=-\frac{b}{a}, c=b$

[B1] line of best fit
[B2] 5 points plotted correctly
Minus one if plot wrongly

(ii) Use the graph to identify the coordinates for the abnormal reading in the table above and estimate its correct y -value. [2]

Abnormal reading (4, 3.71) [B1] must be in coordinates
Estimated value of $y^2 = 13$
Estimated value of $y = 3.61$ [B1]

(iii) Use the graph to estimate the value of a and b. [3]

Y-intercept = 1.1
$b = 1.1$ [B1] use graph

gradient
$-\frac{b}{a}=\frac{15.0-7.02}{7-3}$ [M1] gradient


$-\frac{1.1}{a}=1.995$

$a=-1.1\div 1.995$

$a=-0.551$ [A1]

PartnerInlearning
422
www.testpapersfree.com


Downloaded from SingaKids.com



PartnerInlearning
423
www.testpapersfree.com

Downloaded from SingaKids.com

12 The diagram shows a rock climbing wall. The wall AB, of length 20 m, is to be inclined at an angle θ from the vertical while the wall BC, of length 9 m, is to be inclined at the same angle θ from the horizontal. The height of the whole wall is H m.



(i) Show that $H = 20\cos\theta + 9\sin\theta$. [2]

$\sin\theta = \frac{a}{9}$ [M1]

$a = 9\sin\theta$

$\cos\theta = \frac{b}{20}$ [M1]

$b = 20\cos\theta$

$H = 9\sin\theta + 20\cos\theta\ (shown)$ [AG]

PartnerInlearning
424
www.testpapersfree.com

Downloaded from SingaKids.com

12 **(ii)** Express H in the form $R\sin(\theta+\alpha)$, where $R>0$ and $0°<\alpha<90°$. [4]

$R=\sqrt{9^2+20^2}$ [M1]

$R=\sqrt{481}$

$\tan\alpha=\frac{20}{9}$ [M1]

$\alpha=65.772°$

$H=\sqrt{481}\sin(\theta+65.8°)$ [A1] no A1 if angle is not 1 d.p.

(iii) Find the greatest possible value of H and the value of θ at which this occurs. [3]

Greatest value = $\sqrt{481}$ or 21.9 [B1]

$\sqrt{481}$

$\sin(\theta+65.772°)=1$ [M1] FT

$\theta+65.772°=90°$

$\theta=24.2277°$

$\theta=24.2°$ [A1], M0A0

PartnerInlearning
425
www.testpapersfree.com

Downloaded from SingaKids.com

13 The gradient function of a curve y is given by $2x^2 + x - 6$. [6]

Given that y has a minimum value of $1\frac{3}{8}$, find the equation of the curve.

$\frac{dy}{dx} = 2x^2 + x - 6$

$At \min value, \frac{dy}{dx} = 0$ [M1] $\frac{dy}{dx} = 0$

$(3x-3)(x+2) = 0$

$x = 1.5 \, or \, x = -2$

$\frac{d^2y}{dx^2} = 4x + 1$ [M1] second derivative

$When \, x = -2,$

$\frac{d^2y}{dx^2} = 4(-2) + 1$

$\frac{d^2y}{dx^2} = -7 < 0$ (max)

$When \, x = 1.5,$

$\frac{d^2y}{dx^2} = 4(1.5) + 1$

$\frac{d^2y}{dx^2} = 7 > 0$ (min) [A1] show that $x = 1.5$ is a min pt

$y = \frac{2x^3}{3} + \frac{x^2}{2} - 6x + c$ [M1] integrate to find y

$when \, x = 1.5, y = 1\frac{3}{8},$

$1\frac{3}{8} = \frac{2(1.5)^3}{3} + \frac{(1.5)^2}{2} - 6(1.5) + c$ [M1]

$c = 7$

$y = \frac{2x^3}{3} + \frac{x^2}{2} - 6x + 7$ [A1]

End of Paper

PartnerInlearning
426
www.testpapersfree.com

Downloaded from SingaKids.com